



No RVNL/2016/S&T/ Standard BOQ Amdt. No. 1

Dated 14.06.2017

ED/S&T/Project/Kolkata
All GGMs/GMs & AGMs/JGMs S&T


**Sub: Amendment No.1 to S&T SBOQ 2017 – Modification in description of work,
Explanatory note and Inspection agency of S&T SBOQ item no. 38824**

Modified description of item no. 38824 is to be followed.

SBOQ Item No. 38824	Existing Description	Modified Description
Description Of Work	Supply of 4-Conductor Modular Terminal- WAGO/PHOENIX type.	Supply of 4- Conductor Modular Terminal as per RDSO Spec No. RDSO/SPN/189/2004 or latest.
Explanatory Note	MODULAR TERMINALS: Supply of 4-conductor disconnect terminal block with test & measurement facility, with screw clamp/screwless cage clamp connections suitable for 1.5 to 2.5 sq. mm conductor with current carrying capacity of 16Amp as per RDSO Specn. no. RDSO/SPN/189/2004 or latest RDSO specification of WAGO/PHOENIX type. This also include Supply of required quantity of (i) End Plate (ii) Din Rail (iii) End Stop (iv) Marker & operating tool. End Plate, DIN rail, End stop and marker to be supplied only in the required quantity for above mentioned MODULAR terminals. All samples to be approved by engineer in charge before placing order on vendor.	MODULAR TERMINALS: Supply of 4-conductor disconnect terminal block with test & measurement facility, with screw clamp/screwless cage clamp connections suitable for 1.5 to 2.5 sq. mm conductor with current carrying capacity of 16Amp as per RDSO Specn. no. RDSO/SPN/189/2004 or latest specification from the RDSO approved sources (till approved source list is issued by the RDSO, material can be procured from RDSO recommended sources; issued by RDSO vide letter no. STS/connector vol. III dated 18.09.2014). This also include Supply of required quantity of (i) End Plate (ii) Din Rail (iii) End Stop (iv) Marker & operating tool. End Plate, DIN rail, End stop and marker to be supplied only in the required quantity for above mentioned MODULAR terminals.
Inspection Agency	RITES	RDSO

There is no financial implication.

This has approval of Director Project.


ED(S&T) 14/6/17.

Copy to : 1. DF, DP for kind information please.

2. ED/C&P, ED/Structures, ED/Central, ED/Works, ED/Infra, ED(Metro)/Kolkata, ED/F&A, ED/Elect., ED/Mech., CGM/Lucknow, CGM/Kolkata, GGM/P- for kind information please.

3. All EDs(Projects)/CPMs/GGMs/GMs/AGMs & DGMs/RVNL – for kind information please.